



## OSM/EE DECISION SHEET

Category	Standard:	Clause	Document no.
OFF	EN 62368-1:2014	Annex T.6	OSM-EE 18/3
Subject	Key words		Meeting
Loose enclosure parts inside equipment after impact test	Enclosure, impact test		London 2018
Question			
<p>If a part of the enclosure is loosen/detached as a result of the impact test (T.6) and ends up within the equipment. How should it be handled with regard to creepage and clearance?</p> <p>Should it only be considered to affect creepage and clearance where it lands or should it be moved around (using 10N test of T.2 or similar method)?</p> <p>Is it any different for conductive parts (that might bridge insulation) and none conductive parts (that might create shorter creepage distances than the original construction)?</p>			
Decision			
<p>If conductive loose parts occur after the impact test, it must be checked that it cannot result in any hazardous situation (by placing the loose part in the worst case possible position within the equipment)</p> <p>Confirmed by TC108 at Busan, Korea, Oct 2018</p>			
Explanatory notes			